



**DATA IN PARENTHESES CONFORMS TO CONSTRUCTION RECORDS BY S.W.N. 6/90**

- NOTES:**
- 1 THE CONTRACTOR SHALL LOCATE ALL UTILITIES PRIOR TO CONSTRUCTION AND IS RESPONSIBLE FOR THEIR PROTECTION THROUGHOUT THIS OPERATIONS.
  - 2 THE CONTRACTOR SHALL RESTORE THE SURFACE BY SEEDING AND MULCHING OR HYDROSEEDING IN ACCORDANCE WITH FDOT REQUIREMENTS.
  - 3 ALL VALVES SHALL BE WATEROUS SERIES 500 RESILIENT WEDGE OR APPROVED EQUAL.
  - 4 ALL FIRE HYDRANTS SHALL BE WATEROUS-PAGEX (NO EXCEPTIONS)
  - 5 ALL IRON FITTINGS & PIPE SHALL BE COMPLETELY WRAPPED IN 8MIL THICKNESS BLACK POLYETHYLENE.
  - 6 VALVE BOXES SHALL BE CAST IRON SCREW TYPE ADJUSTABLE WITH "WATER" CAST IN COVER.
  - 7 WATER MAIN SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE SPECIFICATIONS & DETAILS SHOWN ON DWG. NO. 2.

- LEGEND**
- BT- BURIED TELEPHONE
  - CTV- CABLE TV
  - S- SANITARY SEWER
  - W- WATER LINE

**RECORD DRAWING**  
by: LPT 6/26/91

**TYPICAL CROSS-SECTION OF 6\"/>**

SCALE: HOR. 1"=40'  
VERT. 1"=2'

DESIGNED BY: M.J.J. (CL.)  
 DATE: JAN, 1989  
 SCALE: 1"=40'  
 SOC. IN CHARGE: M.J.J.  
 DRAWN BY: M.J.J.  
 CHECKED BY: M.J.J.  
 PROJECT NO: 7499  
 E.P.  
 SARASOTA, FLA. 33582  
 133 SOUTH MCINTOSH RD.  
 CONSULTING ENGINEERS & SURVEYORS  
 BEACH WALK CONDOMINIUM  
 6" WATER LINE EXTENSION  
 FOR: RIVIERA CORPORATION  
 SMALLY, WELLFORD & NALVEN, INC.  
 INDEX NO. 6-2499-019  
 DRAWING NUMBER: 10  
 REVISION: 8